BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 23

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/07/2011-12 Dated: 28-09-2011

Name of Work: Improvements of Concrete Roads and Drains at Byatarayanapura in Ward No. 7 at Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B. R. Danjaya	
				In Figures	In Words
1	216.00	Removing B.S.Slab drain and stacking **(Page No. 24 & Item No. 5.32)**	Sqm	**44.86**	Rupees Forty Four and Eighty Six Paise Only
2	348.30	KSRRB 300-1.1 : Earthwork excavation by manual means in **hard soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Specification No.KRBS 300-1 MORT & H Specification No.301 to 305 **(Page No. 126, Item No.19.1)**	Cum	**135.94**	Rupees One Hundred Thirty Five and Ninety Four Paise Only
3	151.20	Refixing stone slabs of drains and pointing in C.M. (1:3) **(Page No. 24 & Item No. 5.33)**	Sqm	**53.81**	Rupees Fifty Three and Eighty One Paise Only
4	64.80	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete **do 10 cms** thick	Sqm	**319.45**	Rupees Three Hundred Nineteen and Forty Five Paise Only
5	116.36	KSRRB 2900-4.1: Providing and laying in position **plain cement concrete mix 1:4:8** with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. **(Page.12 & Item No. 4.3)**	Cum	**3512.85**	Rupees Three Thousand Five Hundred Twelve and Eighty Five Paise Only
6	106.55	KSRB 4-1.5 : Providing and laying in position **plain cement concrete** of mix **1:1.5:3** using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **(Page No. 12 & Item No. 4.11).**	Cum	**5069.33**	Rupees Five Thousand Sixty Nine and Thirty Three Paise Only

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ವ್ಯಾಪಾರಾಯನಪುರ ವಿಭಾಗ,
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವಲಯ
ಸಂಪಂಗಿರಾಮನಗರ, ಬೆಂಗಳೂರು-92.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B. R. Danjaya	
				In Figures	In Words
7	27.78	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete** of mix **1:1.5:3** with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6. **(Page No. 12 & Item No. 4.11)**	Cum	**5141.83**	Rupees Five Thousand One Hundred Forty One and Eighty Three Paise Only
8	19.45	KSRB 4.9.2 : Providing **T.M.T. Steel reinforcement for R.C.C.** work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. **(Page No. 16 & Item No. 4.46)**	Qtl	**5459.02**	Rupees Five Thousand Four Hundred Fifty Nine and Two Paise Only
9	261.60	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2	Sqm	**209.57**	Rupees Two Hundred Nine and Fifty Seven Paise Only
10	348.30	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	Cum		

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92